



#### <u>Galliford Try – Exceptional Lift Procedure</u>













### **Agenda**



- Why was the Exceptional Lift procedure developed?
- ➤ What is the Exceptional Lift Procedure?
- Implementation
- > Impact
- Summary
- > Q&A


















- No specific guidance on safe installation of bridge beams
- Risk of crushing injuries
- Risk of entrapment
- Risks are enhanced owing to multiple interfaces



- Hazards from situations of temporary instability
- Hazards of lifting large objects
- Hundreds of bridges built each year













- Formalised procedure
- Early stage collaboration
- Sign off by four distinct parties before lift proceeds
- Considering temporary instability
- Management through a Design
  Responsibility Matrix and a Methodology
  Review Matrix















# **Design Responsibility Matrix** covering, inter alia:

- Stability when offloading
- Stability when being landed and until deck cast
- Cantilever falsework design
- Permanent formwork, if any
- Crane foundations

Many designers and interfaces

## Methodology Review Matrix covering, inter alia:

- Location of personnel
- Exclusion zones
- Access
- Layout and Geometry
- Craneage use
- Coordination between multiple subcontractors
















- Lift reviewed during pre-construction phase
- > Lifts assigned as 'normal', or 'exceptional
- > Triggers process with team
- Highlighted to SLT
- ➤ Aim is to eliminate physical interaction with the lift







#### **Implementation**



#### Rugy Radio Link Road

- An Exceptional Lift Procedure was followed on the project
- Meetings commenced 5 months prior to lift
- DRM and MRM used to manage the procedure
- Sign off from GTE, TWC, Health & Safety and Director
- Methodology considered and discussed, approved and signed off
- Installation of temporary stability frames
- Discussion with PWD to resolve reinforcement clashes
- Discussion with PD













#### **Implementation**







#### Grantham Southern Relief Rd Phase 2

- An Exceptional Lift Procedure was followed on the project
- Collaboration started during 2017, built during 2020
- Sign off from GTE, TWC, Health & Safety and Director
- Methodology considered and discussed, approved and signed off
- Installation of temporary stability frames
- Central point of build reviewed and amended
- Working window reviewed and amended













#### **Impact**

- > All lifts undertaken since implementation incident free
- ➤ No unplanned change implemented
- > Each lift delivered ahead of programme
- > Allowed flexibility but without compromise















#### **Summary**

- Not about over complex processes and procedures
- > Focuses on communication and planning
- Assigns owners within the procedure and key milestones
- Built on 'Go/No Go'
- > Focus is always on removing interaction from lift
- > Recognised by BCIA, CCS, CN
- ➤ Company wide adds value













### Q&A





# Thank you for listening







